

ELKHART COUNTY, INDIANA

BOARD OF COUNTY COMMISSIONERS

Bridge 269 Replacement CR1 over Fisher-Gordon Ditch

ITEMIZED PROPOSAL

NO.	SPEC. SECTION	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
1	TP1	Special Right-of-way Conditions	1	L.S.	\$20,000	\$20,000
2	TP2	Mobilization And Demobilization (5% Max)	1	L.S.		
3	TP3	Maintaining Traffic	1	L.S.		
4	TP4	Riprap, Remove	1	L.S.		
5	TP5	Mailbox, Reset	1	EACH		
6	TP6	Fernco Coupler, 12 in	1	EACH		
7	TP7	Pipe, CMP, 12 in	24	L.F.		
8	TP7	Pipe, PVC, 8 in	10	L.F.		
9	TP7	Pipe, RCP, 15 in	155	L.F.		
10	TP8	Guardrail, Transition, Type TGB, Modified	1	EACH		
11	TP9	Mulched Seeding, R	169	S.Y.		
12	TP10	Erosion Control Blanket, R, Seeding Type R	83	S.Y.		
13	105	Construction Engineering	1	L.S.		
14	201	Clearing Right of Way	1	L.S.		
15	202	Present Structure, Remove Portions No.	1	L.S.		
16	202	Concrete, Remove	82	S.Y.		
17	202	Guardrail End Treatment, Remove	4	EACH		
18	203	Excavation, Common	590	C.Y.		
19	205	Temporary Silt Fence	1,155	L.F.		
20	211	B Borrow	55	C.Y.		
21	211	Aggregate For End Bent Backfill	64	C.Y.		
22	301	Compacted Aggregate No 53	380	C.Y.		
23	302	Dense Graded Subbase	40	C.Y.		
24	306	Milling, Transition	23	S.Y.		
25	401	HMA, Type C, Surface, 9.5 mm	93	TON		
26	401	HMA, Type C, Intermediate, 19.0 mm	121	TON		
27	401	HMA, Type C, Base, 25.0 mm	182	TON		
28	406	Asphalt For Tack Coat	2,220	SYS		
29	601	Guardrail, Transition, Type TGB	3	EACH		
30	601	Guardrail End Treatment, OS, TL-2, 31 in	5	EACH		
31	601	Guardrail MGS W-beam, 6 ft 3 in Spacing	100	L.F.		
32	609	Reinforced Concrete Bridge Approach, 12 in	236	S.Y.		
33	610	PCCP For Approaches, 6 in	75	S.Y.		
34	616	Geotextiles	298	S.Y.		
35	616	Riprap, Uniform	89	TON		
36	621	Sodding	446.4	S.Y.		
37	701	Pile, Steel Pipe, 0.375 in, 14 in	630	L.F.		
38	702	Concrete, A, Substructure	22.3	C.Y.		
39	702	Concrete, C, Substructure	97.7	C.Y.		

ELKHART COUNTY, INDIANA

BOARD OF COUNTY COMMISSIONERS

Bridge 269 Replacement CR1 over Fisher-Gordon Ditch

ITEMIZED PROPOSAL

NO.	SPEC. SECTION	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
40	703	Reinforcing Bars, Epoxy Coated	37,763	LBS		
41	703	Threaded Tie Bar Assembly, Epoxy Coated	30	EACH		
42	704	Concrete, C, Superstructure	64.4	C.Y.		
43	706	Concrete Bridge Railing Transition, TPF-1	4	EACH		
44	706	Railing, Concrete, PF-1	91.5	L.F.		
45	706	Railing, Steel, PF-1	109	L.F.		
46	709	Surface Seal	1	L.S.		
47	711	Structural Steel	34,041	LBS		
48	715	Pipe, End Bent Drain, 6 in	120	L.F.		
49	715	Pipe End Section, Dia 15 in	1	EACH		
50	720	Inlet, E7	1	EACH		
51	720	Inlet, F7	1	EACH		
52	801	Road Closure Sign Assembly	4	EACH		
53	801	Construction Sign, A	4	EACH		
54	801	Barricade, III-B	48	L.F.		
55	808	Line, Multi-component, Broken, Yellow, 4 in	532	L.F.		
					TOTAL BID:	