

ADDENDUM NO. 2

ELKHART COUNTY BRIDGE #269 REPLACEMENT PROJECT

June 26, 2020

**BOARD OF COUNTY COMMISSIONERS
ELKHART COUNTY, INDIANA**

TO: All bidders and others to whom Bid Documents for the above referenced Project have been issued

The items included in this Addendum are to become a part of the original Bid Documents as if included therein. Only these items are to be altered. The remainder of the original bid documents maintains validity in their entirety.



Tom Rushlow, P.E.
Elkhart County Highway

A signed copy of this sheet shall be submitted with Proposal Form to document receipt of Addendum No. 2.

Contractor

BID DOCUMENTS

SECTION

REVISION

Bid Item List

The bid item list (Itemized Proposal) has been revised to eliminate Item #38 – Concrete, A, Substructure. This item was for concrete used to fill the shell piling. The INDOT Standard Specifications includes the cost of the concrete with the pile pay item. A revised bid item list (Itemized Proposal) is attached and shall be used with the Contractor’s bid submission.

B Borrow and Aggregate

The Contractor may supply B Borrow and Aggregate from a non-CAPP source as long as the material is shown to meet INDOT Standard Specification requirements to the satisfaction of the Engineer. It is the Contractor’s responsibility to provide proof of the material’s compliance with the INDOT Standard Specifications and receive the Engineer’s approval for use of the material before it is delivered to the site.

ELKHART COUNTY, INDIANA

BOARD OF COUNTY COMMISSIONERS

Bridge 269 Replacement CR1 over Fisher-Gordon Ditch

ITEMIZED PROPOSAL

NO.	SPEC. SECTION	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
1	TP1	Special Right-of-way Conditions	1	L.S.	\$20,000	\$20,000
2	TP2	Mobilization And Demobilization (5% Max)	1	L.S.		
3	TP3	Maintaining Traffic	1	L.S.		
4	TP4	Riprap, Remove	1	L.S.		
5	TP5	Mailbox, Reset	1	EACH		
6	TP6	Fernco Coupler, 12 in	1	EACH		
7	TP7	Pipe, CMP, 12 in	24	L.F.		
8	TP7	Pipe, PVC, 8 in	10	L.F.		
9	TP7	Pipe, RCP, 15 in	155	L.F.		
10	TP8	Guardrail, Transition, Type TGB, Modified	1	EACH		
11	TP9	Mulched Seeding, R	169	S.Y.		
12	TP10	Erosion Control Blanket, R, Seeding Type R	83	S.Y.		
13	105	Construction Engineering	1	L.S.		
14	201	Clearing Right of Way	1	L.S.		
15	202	Present Structure, Remove Portions No.	1	L.S.		
16	202	Concrete, Remove	82	S.Y.		
17	202	Guardrail End Treatment, Remove	4	EACH		
18	203	Excavation, Common	590	C.Y.		
19	205	Temporary Silt Fence	1,155	L.F.		
20	211	B Borrow	55	C.Y.		
21	211	Aggregate For End Bent Backfill	64	C.Y.		
22	301	Compacted Aggregate No 53	380	C.Y.		
23	302	Dense Graded Subbase	40	C.Y.		
24	306	Milling, Transition	23	S.Y.		
25	401	HMA, Type C, Surface, 9.5 mm	93	TON		
26	401	HMA, Type C, Intermediate, 19.0 mm	121	TON		
27	401	HMA, Type C, Base, 25.0 mm	182	TON		
28	406	Asphalt For Tack Coat	2,220	SYS		
29	601	Guardrail, Transition, Type TGB	3	EACH		
30	601	Guardrail End Treatment, OS, TL-2, 31 in	5	EACH		
31	601	Guardrail MGS W-beam, 6 ft 3 in Spacing	100	L.F.		
32	609	Reinforced Concrete Bridge Approach, 12 in	236	S.Y.		
33	610	PCCP For Approaches, 6 in	75	S.Y.		
34	616	Geotextiles	298	S.Y.		
35	616	Riprap, Uniform	89	TON		
36	621	Sodding	446.4	S.Y.		
37	701	Pile, Steel Pipe, 0.375 in, 14 in	630	L.F.		
38	702	Item Deleted Addendum No. 2	n/a	n/a	No Bid	No Bid
39	702	Concrete, C, Substructure	97.7	C.Y.		

ELKHART COUNTY, INDIANA

BOARD OF COUNTY COMMISSIONERS

Bridge 269 Replacement CR1 over Fisher-Gordon Ditch

ITEMIZED PROPOSAL

NO.	SPEC. SECTION	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENSION
40	703	Reinforcing Bars, Epoxy Coated	37,763	LBS		
41	703	Threaded Tie Bar Assembly, Epoxy Coated	30	EACH		
42	704	Concrete, C, Superstructure	64.4	C.Y.		
43	706	Concrete Bridge Railing Transition, TPF-1	4	EACH		
44	706	Railing, Concrete, PF-1	91.5	L.F.		
45	706	Railing, Steel, PF-1	109	L.F.		
46	709	Surface Seal	1	L.S.		
47	711	Structural Steel	34,041	LBS		
48	715	Pipe, End Bent Drain, 6 in	120	L.F.		
49	715	Pipe End Section, Dia 15 in	1	EACH		
50	720	Inlet, E7	1	EACH		
51	720	Inlet, F7	1	EACH		
52	801	Road Closure Sign Assembly	4	EACH		
53	801	Construction Sign, A	4	EACH		
54	801	Barricade, III-B	48	L.F.		
55	808	Line, Multi-component, Broken, Yellow, 4 in	532	L.F.		
					TOTAL BID:	