

ADDENDUM NO. 3

2023 CCMG Project

March 9th, 2023

BOARD OF COUNTY COMMISIONERS

ELKHART COUNTY, INDIANA

TO: All bidders and others to whom Bid Documents for the above referenced Project have been issued

The items included in this Addendum are to become a part of the original Bid Documents as if included therein. Only these items are to be altered. The remainder of the original bid documents maintains validity in their entirety.

ITEM CC8 CALIFORNIA RD (CR 3 N TO CR 1 N)

It is hereby changed from 220 lb/yd² HMA, Type B Surface 12.5 mm and now shall be 275 lb/yd² HMA, Type B Surface 12.5 mm. HMA TONNAGE REMAINS THE SAME AS ORIGINAL BID SHEET READS.

Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds for Tack	Unit	Unit Quantities	Price per Unit	Extension
		CALIFORNIA RD (CR 3 NORTH TO CR 1 NORTH)	7,128	1.36	24.00	19,008				
CC	8	Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	19,008		\$0.00
		Tack Coat					SYS	19,008		\$0.00
		Joint Seal					LFT	7,128		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	2,673		\$0.00
		Pavement Markings, Paint, Solid, White 4"					LF	14,256		\$0.00
		Pavement Markings, Paint, Solid, Yellow 4"					LF	7,128		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	25		\$0.00
		Pavement Marking, Thermoplastic, White, Right Turn, Arrow					EA	2		\$0.00
		#53 Gravel Shoulders					TON	500		\$0.00
		Mailbox, Relocate					EA	1		\$0.00
TOTAL FOR ITEM									\$0.00	

No other terms or conditions of the Contract are negated or changed as a result of the Addendum.

Contractor Acknowledgement