

**Courthouse Redundancy Fiber Optic Project**  
**Elkhart County Highway Department**

**ADDENDUM NO. 1**

**Answers to Prebid Questions**

1. What are the splicing requirements for tie-ins to the existing fiber? The contractor will not splice to the existing fiber. The new fiber cable is to be coiled and spliced in house at a later date.
2. What are the depths for the conduit? 32-48 inches
3. What type of handholes will be installed? 24x36x30 <https://www.channell.com/product/bulk-4/>
4. Will the contractor supply all the material? Yes
5. Will the contractor be responsible for permitting? Yes.

