

Elkhart County 2024-1 CCMG Paving Program

ADDENDUM NO. 1

2024-1 CCMG Paving Program

May 8, 2024

BOARD OF COUNTY COMMISSIONERS

ELKHART COUNTY, INDIANA

TO: All bidders and others to whom Bid Documents for the above referenced Project have been issued.

The items included in this Addendum are to become a part of the original Bid Documents as if included therein. Only these items are to be altered. The remainder of the original bid documents maintains validity in their entirety.

1. The TP2 section of the Specifications have been revised and reissued, as follows:

The following road sections to not be under construction between Friday May 31, 2024 to Sunday June 2, 2024.

- a. CC1: CR 22 between CR 37 and CR 35
 - b. CC4: CR 4 between CR 131 and CR 35
 - c. CC5: CR 35 between SR 120 and Bridge
 - d. CC9: CR 10 between SR 13 and CR 43
2. Asphalt millings shall be delivered to the Elkhart County Landfill off of CR 26, pictured in aerial below. Contractor may retain any millings after it reaches capacity as directed by Highway Department, Contractor shall coordinate with Kyle Wagner for specific instructions for dump location.

Kyle Wagner: kwagner@elkcohw.org, (574) 369-9261 (cell)

Elkhart County 2024-1 CCMG Paving Program



3. Pre-Bid Meeting Minutes have been attached to Addendum No.1

4. The Field Directives have been revised and reissued, as follows:

ALT 1 PUMPKIN VINE TRAIL (COUNTY ROAD 28 – STATE ROAD 4) PAVE 2” BEGIN ON NORTH EDGELINE OF THE PUMPKIN VINE TRAIL SOUTH OF COUNTY ROAD 28 AND END AT SOUTH EDGELINE OF THE PUMPKIN VINE TRAIL NORTH OF STATE ROAD 4. EXISTING GRAVEL SURFACE SHALL BE PROFILED USING ROAD GRADER IN PREPARATION FOR ASPHALT PAVING. CONTRACTOR SHALL ADD COMPACTED #53 AGGREGATE WHERE NECESSARY TO FILL IN LOW SPOTS AT DIRECTION OF ENGINEER (UNDISTRIBUTED ITEM HAS BEEN INCLUDED FOR THIS WORK). INCLUDE MILLED BUTT JOINTS FOR SMOOTH TRANSITION AT EACH END. PAVE FULL DEPTH OVER THE TWO EXISTING ASPHALT PAVEMENT FIELD CROSSINGS LOCATED ON THE TRAIL TO ENSURE SMOOTH TRANSITION. PROTECT ALL BENCHES AND TRASH RECEPTACLES THROUGH OUT TRAIL AND INSTALL NO. 11 F LIMESTONE TO CREATE SMOOTH TRANSITION TO NEW PAVEMENT IN COMPLIANCE WITH THE AMERICANS WITH DISABILITIES ACT.

ALL DEBRIS GENERATED THROUGH THE CONSTRUCTION PROCESS, SHALL BE REMOVED AT COMPLETION OF PAVING. +/- 2 FOOT TOPSOIL SHOULDERS SHALL BE ADDED TO TRANSITION NEW PAVEMENT TO EXISTING GRADE. MILLED TRANSITIONS OF ASPHALT DRIVES SHALL BE INCLUDED IN PREP COST. ALL TRAFFIC CONTROL, MOBILIZATION/DEMOLIBIZATION, AND ANY INCENDENTIALS NOT SPECIFIED AS LINE ITEMS, SHALL BE INCLUDED IN PREP COST.

(1.68 MILES)

5. The bid for has been revised and reissued, as follows:

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	1	County Road 22 (County Road 35 to County Road 37)	6,917	1.31	26.00	22,324				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	22,324		\$0.00
		Tack Coat					SYS	22,324		\$0.00
		Joint Seal					LFT	6,917		\$0.00
		220 lb/yd ² HMA, Type C Surface 12.5 mm					TON	2,456		\$0.00
		Line, Paint, Solid, White 4"					LF	13,834		\$0.00
		Line, Paint, Solid, Yellow 4"					LF	12,230		\$0.00
		#53 Gravel Shoulders					TON	400		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	2	County Road 22 (County Road 28 to Goshen City Limits)	5,386	1.02	26.00	17,900				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	17,901		\$0.00
		Tack Coat					SYS	17,901		\$0.00
		Joint Seal					LFT	5,386		\$0.00
		220 lb/yd ² HMA, Type C Surface 12.5 mm					TON	1,970		\$0.00
		Line, Paint, Solid, White 4"					LF	13,834		\$0.00
		Line, Paint, Solid, Yellow 4"					LF	12,230		\$0.00
		#53 Gravel Shoulders					TON	400		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	3	County Road 11 from Ernest St to County Road 6	1,980	0.38	24.00	5,280				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	5,280		\$0.00
		Tack Coat					SYS	5,280		\$0.00
		Joint Seal					LFT	1,980		\$0.00
		220 lb/yd ² HMA, Type C Surface 12.5 mm					TON	581		\$0.00
		Line, Paint, Solid, White 4"					LF	3,960		\$0.00
		Line, Paint, Solid, Yellow 4"					LF	3,705		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	30		\$0.00
		Pavement Markings, Thermoplastic, White, Straight-Right Combo Arrow					EA	1		\$0.00
Pavement Markings, Thermoplastic, White, Left Turn Arrow					EA	1		\$0.00		
#53 Gravel Shoulders					TON	200		\$0.00		
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	4	County Road 4 from County Road 131 to Country Road 35	9,504	1.80	26.00	27,456				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	27,456		\$0.00
		Tack Coat					SYS	27,456		\$0.00
		Joint Seal					LFT	9,504		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	3,021		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	8,079		\$0.00
		Pavement Markings, Thermoplastic, White, R X R					EA	2		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	40		\$0.00
		#53 Gravel Shoulders					TON	400		\$0.00
TOTAL FOR ITEM									\$0.00	

								BID		
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	5	County Road 35 from State Road 120 to Bridge	5,544	1.05	24.00	14,784				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	14,784		\$0.00
		Joint Seal					LFT	5,544		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	2,033		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	6,950		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

								BID		
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	6	County Road 23 from US 20 to County Road 18	5,280	1.00	24.00	14,080				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	14,080		\$0.00
		Joint Seal					LFT	5,280		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,936		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	4,484		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

								BID		
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	7	County Road 7 from County Road 44 to State Road 119	2,376	0.45	24.00	6,336				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	6,336		\$0.00
		Joint Seal					LFT	2,376		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	872		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	2,680		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

								BID		
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	8	County Road 21 from County Road 2 to Michigan State Line	2,006	0.38	24.00	5,350				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	5,350		\$0.00
		Joint Seal					LFT	2,006		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	736		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	9	County Road 10 from State Road 13 to County Road 43	5,597	1.06	24.00	14,925				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	14,925		\$0.00
		Tack Coat					SYS	14,925		\$0.00
		Joint Seal					LFT	5,597		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,642		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	10	County Road 9 from US Highway 6 to County Road 52	5,296	1.00	24.00	14,122				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	14,122		\$0.00
		Joint Seal					LFT	5,296		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,942		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	11	County Road 11 from County Road 42 to State Road 119	4,404	0.83	24.00	11,743				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	11,743		\$0.00
		Joint Seal					LFT	4,404		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,615		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	12	County Road 46 from W County Line Rd to County Road 1	5,269	1.00	24.00	14,052				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	14,052		\$0.00
		Joint Seal					LFT	5,269		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,933		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	13	County Road 50 from W County Line Rd to County Road 1	5,296	1.00	24.00	14,122				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	14,122		\$0.00
		Joint Seal					LFT	5,296		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,942		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14	County Road 133 from RR Crossing to State Line Rd	4,704	0.89	24.00	12,545				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	12,545		\$0.00
		Joint Seal					LFT	4,704		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,725		\$0.00
		Pavement Markings, Thermoplastic, White, R X R					EA	2		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	20		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	15	Road 127 from County Road 46 to County Road 44 - PAVING EXCEPTION FOR BRID	4,963	0.94	24.00	13,235				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	13,235		\$0.00
		Tack Coat					SYS	13,235		\$0.00
		Joint Seal					LFT	4,963		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,456		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	16	Grace Lane from County Road 20 to End	300	0.06	22.00	733				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	733		\$0.00
		Tack Coat					SYS	733		\$0.00
		Joint Seal					LFT	300		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	81		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	17	Circle Lane from Homeland Rd to Sheri Ln	1,674	0.32	24.00	4,464				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	4,464		\$0.00
		Tack Coat					SYS	4,464		\$0.00
		Joint Seal					LFT	1,674		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	492		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	18	Sheri Ln from Holiday Dr to End	1,320	0.25	24.00	3,520				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	3,520		\$0.00
		Tack Coat					SYS	3,520		\$0.00
		Joint Seal					LFT	1,320		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	388		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	19	Montrose Park Drive from Homeland Rd to Oak Leaf Dr.	2,087	0.40	24.00	5,565				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	5,565		\$0.00
		Tack Coat					SYS	5,565		\$0.00
		Joint Seal					LFT	2,087		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	613		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

TOTAL CCMG COST \$0.00

										BID	
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds for Tack	Unit	Unit Quantities	Price per Unit	Extension	
EC	1	Bridge Deck Resurface	5,544	1.05	24.00	14,784					
		Resurface Bridge Deck #326 With Membrane (CC15 - County Road 127)					LS	1		\$0.00	
		Monument Replacement					EACH	1		\$0.00	
		TOTAL FOR ITEM									\$0.00

										BID	
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension	
EC	2	Bridge Deck Resurface	240	1.05	24.00	640					
		Resurface Bridge Deck #184 (County Road 43 between US 20 and County Road 18) Prep Cost					LS	1		\$0.00	
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	71		\$0.00	
		Tack Coat					SYS	640		\$0.00	
		Joint Seal					LFT	240		\$0.00	
		Monument Replacement					EACH	1		\$0.00	
TOTAL FOR ITEM									\$0.00		

										BID	
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension	
EC	3	Bridge Deck Resurface	250	1.05	24.00	667					
		Resurface Bridge Deck #232 With Membrane (County Road 11 between County Road 36 and County Road 32) Prep Cost					LS	1		\$0.00	
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	74		\$0.00	
		Tack Coat					SYS	640		\$0.00	
		Joint Seal					LFT	250		\$0.00	
		Monument Replacement					EACH	1		\$0.00	
TOTAL FOR ITEM									\$0.00		

										BID	
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension	
EC	4	Bridge Deck Resurface	200	1.05	24.00	533					
		Resurface Bridge Deck #291 With Membrane (County Road 13 between County Road 52 and County Road 54) Prep Cost					LS	1		\$0.00	
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	59		\$0.00	
		Tack Coat					SYS	533		\$0.00	
		Joint Seal					LFT	200		\$0.00	
		Monument Replacement					EACH	1		\$0.00	
TOTAL FOR ITEM									\$0.00		

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension
EC	5	Bridge Deck Resurface	240	1.05	24.00	640				
		Resurface Bridge Deck #257 (County Road 40 between County Road 1 and County Road 1) Prep Cost					LS	1		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	71		\$0.00
		Tack Coat					SYS	533		\$0.00
		Joint Seal					LFT	200		\$0.00
		Monument Replacement					EACH	1		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	6	County Road 31 PATCH	16	0.003	4.00	7				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling					LFT	24		\$0.00
		Tack Coat					SYS	7		\$0.00
		Joint Seal					LFT	24		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	2		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
ALT	1	Pumpkin Vine Trail (SR 4 - CR 28)	8,870	1.68	12.00	11,827				
		Prep Cost (Overlay)					LS	1		\$0.00
		Joint Seal					LFT	24		\$0.00
		Limestone No. 11F					TON	20		\$0.00
		220 lb/yd ² HMA, Type B Intermediate 12.5 mm					TON	1,301		\$0.00
		165 lb/yd ² HMA, Type B Surface 9.5 mm					TON	976		\$0.00
		#53 Compacted Aggregate for Subbase (Undistributed)					TON	200		\$0.00
		Topsoil for Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	



2024-1 CCMG Paving Program / 2024 Wedging Program

Pre-Bid Meeting

Elkhart County Highway Department
May 2nd, 2024, 10:00 AM

Agenda

1. Introduction

- a. Elkhart County Staff
- b. Contact Person:
Primary Contact: Mario Soto Luna, Elkhart County
msotoluna@elkcohw.org (email). (574)312-8001 (cell)
County Engineer: Charlie McKenzie, P.E. Elkhart County
Cmckenzie@elkcohw.org, (574)533-0538 (office)

Elkhart County will need to be contacted before you show up on site and will need to be notified in advance of all paving. (Schedule of 2024-1 CCMG Paving Program and 2024 Wedging Program must be provided by Contractor no later than The Pre-Construction Meeting).

2. Overview of Project – 2024-1 CCMG Paving Program

- a. Contract time: May 27th to October 4th, 2024. Earlier start may be permitted if award and contract documents are in place.
- b. Bid opening at Commissioners Meeting May 13th, 2024 at 9:00 a.m.
- c. Project Description – Just Over 22 miles of paving, combination of full depth reclamation, mill and overlay, Bridge resurface, and overlay the Pumpkin Vine Trail.

3. Overview of Project – 2024 Wedging Program

- a. Contract time: May 27th to July 19th, 2024. Earlier start may be permitted if award and contract documents are in place.
- b. Bid opening at Commissioners Meeting May 20th, 2024 at 9:00 a.m.
- c. Project Description – Just Over 24 miles of wedging paving.

4. Maintenance of Traffic – follow MUTCD.

- a. Contractor is responsible for all Maintenance of Traffic (See TP 9 in Specifications), i.e., flaggers, barricades, etc.
- b. Barricades are to be checked daily at the beginning and end of each day, removed or reset if needed and promptly replaced if moved during the daily construction process
- c. Unnecessary traffic must be kept to a minimum, work zone safety is paramount
- d. Contractor is responsible for haul trucks and other subcontractors

5. Time of Completion

- a. Completion date of July 19th, 2024.



- b. No extra days for weather, supply delays, utility conflicts, shop drawing review, etc.
Liquidated damages: \$1000 per day
6. Measurement of Quantities
 - a. Measurements, as called out in the Bid Documents
7. Paving
 - a. No extra time will be given for weather delays.
 - b. New Asphalt material specification.
8. Demonstration of Prior Experience
 - a. All bidders must submit a list of similar projects completed within last two years describing project scope, work completed by bidder's forces, contract amount, and owner contacts
9. Use of Sub Contractors
 - a. Any sub-contractors to be used on the project must be listed in the bid submittal.
10. Addendums will be promptly posted on web site. It is the Contractor's responsibility to check website for updates.
 - a. Must acknowledge all addendums on bid sheet
 - b. Addendums have been known to be posted less than 24-hrs before bid due. Check the website often.
 - c. May possibly be at least one addendum after this meeting.
11. Pay estimates
 - a. 10 % retainage
 - b. Monthly estimates allowed. Submit At least 15 days before each regularly scheduled County Commissioners Meeting.
12. Bids due on Monday, May 13th, 2024 for the 2024-1 CCMG, and May 20th, 2024 for the 2024 Wedging Program at County Commissioner's office (not 610 Steury). Will be opened and read at the meeting at 9:00 AM.
13. Elkhart County reserves the right to award individual segments within the bid package at its discretion.
14. Tandem Bicycle Ride in Elkhart County – We would like to not pave during Friday May 31 – Sun June 2, 2024 in the following roads
 - a. 2024 Wedging:
 - i. CR 8 (CR 10 – Middlebury Town Limits)
 - ii. CR 10 (CR 39 – SR 13)
 - iii. CR 33 (CR 14 – CR 131)



- iv. CR 33 (CR 26 – CR 20)
- b. 2024-1 CCMG
 - i. CR 4 (CR 131 – CR 35)
 - ii. CR 35 (SR 120 – Bridge)
 - iii. CR 10 (SR 13 – CR 43)
 - iv. CR 22 (CR 37 – CR 35)

An addendum will be issued.

15. ALT 1: The Pumpkin Vine Trail is being bid as an alternative. With a different Notice to Proceed date.

16. Millings will be delivered to the Elkhart County Landfill on County Road 7.

- a. Location with aerial to be posted on addendum.

17. Bidder Questions / Comments

