

ADDENDUM NO. 1

2024-2 Paving Program

October 10, 2024

BOARD OF COUNTY COMMISSIONERS

ELKHART COUNTY, INDIANA

TO: All bidders and others to whom Bid Documents for the above referenced Project have been issued.

The items included in this Addendum are to become a part of the original Bid Documents as if included therein. Only these items are to be altered. The remainder of the original bid documents maintains validity in their entirety.

1. Asphalt millings shall be delivered to the Elkhart County Landfill off of CR 26, pictured in aerial below. Contractor may retain any millings after it reaches capacity as directed by Highway Department, Contractor shall coordinate with Kyle Wagner or Jay Brown for specific instructions for dump location.

Kyle Wagner: kwagner@elkcohw.org, (574) 369-9261 (cell)

Jay Brown: jbrown@elkcohw.org, (574) 312-4022 (cell)

Elkhart County 2024-2 Paving Program



- 2. Pre-Bid Meeting Minutes have been attached to Addendum No.1
- 3. The bid for has been revised and reissued, as follows:

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	1	County Road 10 (County Road 3 to County Road 6)	8,607	1.63	26.00	27,207				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	27,207		\$0.00
		Tack Coat					SYS	27,207		\$0.00
		Joint Seal					LFT	8,607		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	2,993		\$0.00
		Line, Paint, Solid, White 4"					LF	5,174		\$0.00
		Line, Paint, Solid, Yellow 4"					LF	17,214		\$0.00
		#53 Gravel Shoulders					TON	400		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	2	County Road 33 (County Road 29 to County Road 4)	4,640	0.38	24.00	12,373				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	12,373		\$0.00
		Joint Seal					LFT	4,640		\$0.00
		275 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,702		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	30		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	3	Riverbrook Ln and Brock Ln	1,786	0.34	24.00	4,763				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	4,763		\$0.00
		Tack Coat					SYS	4,763		\$0.00
		Joint Seal					LFT	1,786		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	524		\$0.00
		Shoulders (Topsoil)					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	4	Heritage Rd (Clover Ln, Buttercup Ln, Alpine Ln, Country Ln)	1,930	0.37	24.00	5,147				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	5,147		\$0.00
		Tack Coat					SYS	5,147		\$0.00
		Joint Seal					LFT	1,930		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	567		\$0.00
		Shoulders (Topsoil)					TON	200		\$0.00
		TOTAL FOR ITEM								

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	5	alwood Dr, Mark Manor Dr, Leslie Ln, Chelsea Ct, Bradford Ct, Kingston Ct, Ashby Ct, Bishop Ct, Bolton Ct, Cambrid	6,798	1.29	24.00	18,128				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	18,128		\$0.00
		Tack Coat					SYS	18,128		\$0.00
		Joint Seal					LFT	6,798		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,995		\$0.00
		Shoulders (Topsoil)					TON	200		\$0.00
		TOTAL FOR ITEM								

Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	6	El Paco Sub (Lantz Blvd, Frank Ct, Mars Dr, Driftwood Dr, Miller Dr)	6,440	1.22	24.00	17,173				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	17,173		\$0.00
		Tack Coat					SYS	17,173		\$0.00
		Joint Seal					LFT	6,440		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,890		\$0.00
		Shoulders (Topsoil)					TON	200		\$0.00
		TOTAL FOR ITEM								
BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	7	Gunder Rd	2,770	0.52	24.00	7,387				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	7,387		\$0.00
		Tack Coat					SYS	7,387		\$0.00
		Joint Seal					LFT	2,770		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,016		\$0.00
		Shoulders (Topsoil)					TON	200		\$0.00
		TOTAL FOR ITEM								
BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
EC	8	Amberwood Dr, Lacey Ln	4,963	0.94	24.00	13,235				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	13,235		\$0.00
		Tack Coat					SYS	13,235		\$0.00
		Joint Seal					LFT	4,963		\$0.00
		220 lb/yd ² HMA, Type B Surface 12.5 mm					TON	1,456		\$0.00
		Shoulders (Topsoil)					TON	200		\$0.00
		TOTAL FOR ITEM								
TOTAL EC COST									\$0.00	



2024-2 Paving Program

Pre-Bid Meeting Minutes

Elkhart County Highway Department
October 10th, 2024, 10:00 AM

Agenda

1. Introduction

- a. Elkhart County Staff
- b. Contact Person:
Primary Contact: Mario Soto Luna, Elkhart County
msotoluna@elkcohw.org (email). (574)312-8001 (cell)

Elkhart County will need to be contacted before you show up on site and will need to be notified in advance of all paving. (Schedule of 2024-2 Paving Program must be provided by Contractor no later than The Pre-Construction Meeting).

2. Overview of Project – 2024-2 Paving Program

- a. Contract time: November 5th to May 9th, 2025. Earlier start may be permitted if award and contract documents are in place.
- b. Bid opening at Commissioners Meeting October 21st, 2024 at 9:00 a.m.
- c. Project Description – Just Over 6 miles of paving, combination of full depth reclamation and mill and overlay.

3. Maintenance of Traffic – follow MUTCD.

- a. Contractor is responsible for all Maintenance of Traffic (See TP 9 in Specifications), i.e., flaggers, barricades, etc.
- b. Barricades are to be checked daily at the beginning and end of each day, removed or reset if needed and promptly replaced if moved during the daily construction process
- c. Unnecessary traffic must be kept to a minimum, work zone safety is paramount
- d. Contractor is responsible for haul trucks and other subcontractors

4. Time of Completion

- a. Completion date of May 9th, 2025.
- b. No extra days for weather, supply delays, utility conflicts, shop drawing review, etc.
Liquidated damages: \$1000 per day

5. Measurement of Quantities

- a. Measurements, as called out in the Bid Documents

6. Paving



- a. No extra time will be given for weather delays.
 - b. New Asphalt material specification.

7. Demonstration of Prior Experience
 - a. All bidders must submit a list of similar projects completed within last two years describing project scope, work completed by bidder's forces, contract amount, and owner contacts

8. Use of Sub Contractors
 - a. Any sub-contractors to be used on the project must be listed in the bid submittal.

9. Addendums will be promptly posted on web site. It is the Contractor's responsibility to check website for updates.
 - a. Must acknowledge all addendums on bid sheet
 - b. Addendums have been known to be posted less than 24-hrs before bid due. Check the website often.
 - c. May possibly be at least one addendum after this meeting.

10. Pay estimates
 - a. 10 % retainage
 - b. Monthly estimates allowed. Submit At least 15 days before each regularly scheduled County Commissioners Meeting.

11. Bids due on Monday, October 21st, 2024 for the 2024-2 Paving Program, at County Commissioner's office (not 610 Steury). Will be opened and read at the meeting at 9:00 AM.

12. Elkhart County reserves the right to award individual segments within the bid package at its discretion.

13. Millings will be delivered to the Elkhart County Landfill off of County Road 7.

14. Bidder Questions / Comments
 - EC 6 – to be scheduled as the last one to be completed.