

Elkhart County 2025-1 CCMG Paving Program

ADDENDUM NO. 3

2025-1 CCMG Paving Program

April 11, 2025

BOARD OF COUNTY COMMISSIONERS

ELKHART COUNTY, INDIANA

TO: All bidders and others to whom Bid Documents for the above referenced Project have been issued.

The items included in this Addendum are to become a part of the original Bid Documents as if included therein. Only these items are to be altered. The remainder of the original bid documents maintains validity in their entirety.

1. The bid form has been revised and reissued, as follows:

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	1	County Road 13 from County Road 18 to County Road 16	2,820	0.53	26.00	8,146				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	8,146		\$0.00
		Tack Coat					SYS	8,146		\$0.00
		Joint Adhesive					LFT	2,820		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	897		\$0.00
		Adjust Casting to Grade					EACH	3		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	5,640		\$0.00
		Line, Paint, Solid, White 4"					LFT	5,640		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM										\$0.00

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	2	County Road 46 from State Road 19 to County Road 11	15,840	3.00	24.00	42,240				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	42,240		\$0.00
		Tack Coat					SYS	42,240		\$0.00
		Joint Adhesive					LFT	15,840		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	4,647		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	5,025		\$0.00
		Line, Paint, Dashed, Yellow 4"					LFT	3,960		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	12		\$0.00
		#53 Gravel Shoulders					TON	600		\$0.00
TOTAL FOR ITEM										\$0.00

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	3	County Road 28 from County Road 13 to County Road 11 - PAVING EXCEPTION FOR BRIDGE #149	5,280	1.00	24.00	14,080				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	14,080		\$0.00
		Joint Adhesive					LFT	5,280		\$0.00
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	1,936		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	5,280		\$0.00
		Line, Paint, Dashed, Yellow 4"					LFT	927		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	12		\$0.00
TOTAL FOR ITEM										\$0.00

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	4	County Road 7 from County Road 52 to County Road 46	13,200	2.50	24.00	35,200				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	35,200		\$0.00
		Tack Coat					SYS	35,200		\$0.00
		Joint Adhesive					LFT	13,200		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	3,872		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	4,993		\$0.00
		Line, Paint, Dashed, Yellow 4"					LFT	927		\$0.00
		#53 Gravel Shoulders					TON	500		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	5A	County Road 111 from County Road 20 to Shaffer Ave	2,144	0.41	22.00	5,240				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	5,240		\$0.00
		Tack Coat					SYS	5,240		\$0.00
		Joint Adhesive					LFT	2,144		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	577		\$0.00
		Line, Paint, Solid, Yellow 4"					LFT	4,287		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	6	County Road 7 from County Road 38 to County Road 36	5,269	1.00	22.00	12,881				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	12,881		\$0.00
		Joint Adhesive					LFT	5,270		\$0.00
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	1,772		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	7	County Road 24 from State Road 15 to County Road 27	6,547	1.24	22.00	16,004				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	16,005		\$0.00
		Joint Adhesive					LFT	6,548		\$0.00
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	2,201		\$0.00
		#53 Gravel Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension			
CC	8	County Road 11 from County Road 48 to County Road 46	5,280	1.00	22.00	12,907							
		Prep Cost (Grind)					LS	1		\$0.00			
		Asphalt Grinding Full Depth					SYS	12,907		\$0.00			
		Joint Adhesive					LFT	5,280		\$0.00			
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	1,775		\$0.00			
		#53 Gravel Shoulders					TON	200		\$0.00			
		TOTAL FOR ITEM									\$0.00		

										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension			
CC	9	County Road 46 from State Road 19 to County Road 1	10,560	2.00	24.00	28,160							
		Prep Cost (Grind)					LS	1		\$0.00			
		Asphalt Grinding Full Depth					SYS	28,160		\$0.00			
		Joint Adhesive					LFT	10,560		\$0.00			
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	3,872		\$0.00			
		#53 Gravel Shoulders					TON	200		\$0.00			
		TOTAL FOR ITEM									\$0.00		

										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension			
CC	10	County Road 11 from County Road 11N to County Road 11S	2,534	0.48	24.00	6,758							
		Prep Cost (Mill)					LS	1		\$0.00			
		Asphalt Milling (2 inches)					SYS	6,759		\$0.00			
		Tack Coat					SYS	2,535		\$0.00			
		Joint Adhesive					LFT	2,535		\$0.00			
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	744		\$0.00			
		Line, Paint, Solid, Yellow 4"					LFT	1,815		\$0.00			
		Line, Paint, Dashed, Yellow 4"					LFT	634		\$0.00			
		#53 Gravel Shoulders					TON	200		\$0.00			
TOTAL FOR ITEM									\$0.00				

										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension			
CC	11	County Road 48 from County Road 11 to County Road 13	5,280	1.00	22.00	12,907							
		Prep Cost (Grind)					LS	1		\$0.00			
		Asphalt Grinding Full Depth					SYS	12,907		\$0.00			
		Joint Adhesive					LFT	5,280		\$0.00			
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	1,775		\$0.00			
		#53 Gravel Shoulders					TON	400		\$0.00			
		TOTAL FOR ITEM									\$0.00		

										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension			
CC	12	County Road 146 from County Road 29 to County Road 31	5,280	1.00	22.00	12,907							
		Prep Cost (Grind)					LS	1		\$0.00			
		Asphalt Grinding Full Depth					SYS	12,907		\$0.00			
		Joint Adhesive					LFT	5,280		\$0.00			
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	1,775		\$0.00			
		#53 Gravel Shoulders					TON	400		\$0.00			
		TOTAL FOR ITEM									\$0.00		

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	13	County Road 50 from County Road 29 to County Road 31	3,221	0.61	22.00	7,873				
		Prep Cost (Grind)					LS	1		\$0.00
		Asphalt Grinding Full Depth					SYS	7,874		\$0.00
		Joint Adhesive					LFT	3,221		\$0.00
		275 lb/yd ² HMA, 12.5 mm, Surface, Type B, 58S-28					TON	1,083		\$0.00
		#53 Gravel Shoulders					TON	400		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14A	Forrest Lakes Dr from State Road 120 to End	4,594	0.87	26.00	13,270				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	13,271		\$0.00
		Tack Coat					SYS	13,271		\$0.00
		Joint Adhesive					LFT	4,594		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	1,460		\$0.00
		Topsoil Shoulders					TON	200		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14B	Poplar Ln from End to End	317	0.06	24.00	2,125				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	2,126		\$0.00
		Tack Coat					SYS	2,126		\$0.00
		Joint Adhesive					LFT	317		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	234		\$0.00
		Topsoil Shoulders					TON	50		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14C	Crabapple Ln from Forrest Lakes Dr to End	407	0.08	24.00	1,516				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,516		\$0.00
		Tack Coat					SYS	1,516		\$0.00
		Joint Adhesive					LFT	407		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	167		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14D	Redwood Ln from Forrest Lakes Dr to End	298	0.06	24.00	1,165				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,166		\$0.00
		Tack Coat					SYS	1,166		\$0.00
		Joint Adhesive					LFT	298		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	129		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
TOTAL FOR ITEM									\$0.00	

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14E	Juniper Ln from Forrest Lakes Dr to End	317	0.06	24.00	1,626				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,627		\$0.00
		Tack Coat					SYS	1,627		\$0.00
		Joint Adhesive					LFT	317		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	179		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14F	Cypress Ln from Forrest Lakes Dr to End	244	0.05	24.00	995				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	996		\$0.00
		Tack Coat					SYS	996		\$0.00
		Joint Adhesive					LFT	244		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	110		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14G	Aspen Ln from Forrest Lakes Dr to End	264	0.05	24.00	1,069				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,070		\$0.00
		Tack Coat					SYS	1,070		\$0.00
		Joint Adhesive					LFT	264		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	118		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	14H	Butternut Dr from Forrest Lakes Dr to End	558	0.11	24.00	1,922				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,922		\$0.00
		Tack Coat					SYS	1,922		\$0.00
		Joint Adhesive					LFT	558		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	212		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	15A	Timber Ridge Dr from County Road 19 to Beech Grove Dr	808	0.15	24.00	2,154				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	2,155		\$0.00
		Tack Coat					SYS	2,155		\$0.00
		Joint Adhesive					LFT	808		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	237		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	15B	Red Oak Ct from Timber Ridge Dr to End	343	0.06	24.00	1,349				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,350		\$0.00
		Tack Coat					SYS	1,350		\$0.00
		Joint Adhesive					LFT	343		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	149		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	15C	Sugar Maple Ct from Timber Ridge Dr to End	416	0.08	24.00	1,608				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	1,608		\$0.00
		Tack Coat					SYS	1,608		\$0.00
		Joint Adhesive					LFT	416		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	177		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

		BID								
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yards	Unit	Unit Quantities	Price per Unit	Extension
CC	15D	Beech Grove Dr from End to End	920	0.17	24.00	3,216				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	3,216		\$0.00
		Tack Coat					SYS	3,216		\$0.00
		Joint Adhesive					LFT	920		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	354		\$0.00
		Topsoil Shoulders					TON	25		\$0.00
		TOTAL FOR ITEM								

Total CCMG 2025-1 \$0.00

										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds for Tack	Unit	Unit Quantities	Price per Unit	Extension			
EC	1	Bridge Deck Resurface	5,544	1.05	24.00	14,784							
		Resurface Bridge Deck #149 With Membrane (CC4 - County Road 28)					LS	1		\$0.00			
		Monument Replacement					SYS	1		\$0.00			
		TOTAL FOR ITEM									\$0.00		
										BID			
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension			
EC	2	Clayton St from Shaffer Ave to Cul-De-Sac	422	0.08	22.00	1,320							
		Prep Cost (Mill)					LS	1		\$0.00			
		Asphalt Milling (2 inches)					SYS	1,320		\$0.00			
		Tack Coat					SYS	1,320		\$0.00			
		Joint Adhesive					LFT	422		\$0.00			
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	146		\$0.00			
		#53 Gravel Shoulders					TON	200		\$0.00			
TOTAL FOR ITEM									\$0.00				
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension			
EC	3	Bridge Deck Resurface	250	1.05	26.00	722							
		Resurface Bridge Deck #183 With Membrane (County Road 43 between County Road 16 and US 20)					LS	1		\$0.00			
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	80		\$0.00			
		Tack Coat					SYS	722		\$0.00			
		Joint Adhesive					LFT	250		\$0.00			
		Monument Replacement					SYS	1		\$0.00			
TOTAL FOR ITEM									\$0.00				
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension			
EC	4	Bridge Deck Resurface	250	1.05	26.00	722							
		Resurface Bridge Deck #206 With Membrane (County Road 33 between County Road 38 and County Road 40)					LS	1		\$0.00			
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	80		\$0.00			
		Tack Coat					SYS	722		\$0.00			
		Joint Adhesive					LFT	250		\$0.00			
		Monument Replacement					SYS	1		\$0.00			
TOTAL FOR ITEM									\$0.00				
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension			
EC	5	Bridge Deck Resurface	250	1.05	26.00	722							
		Resurface Bridge Deck #210 (County Road 31 between County Road 138 and County Road 38)					LS	1		\$0.00			
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	80		\$0.00			
		Tack Coat					SYS	722		\$0.00			
		Joint Adhesive					LFT	250		\$0.00			
		Monument Replacement					SYS	1		\$0.00			
TOTAL FOR ITEM									\$0.00				
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension			
EC	6	Bridge Deck Resurface	250	1.05	26.00	722							
		Resurface Bridge Deck #351 (County Road 43 between County Road 44 and County Road 46)					LS	1		\$0.00			
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	80		\$0.00			
		Tack Coat					SYS	722		\$0.00			
		Joint Adhesive					LFT	250		\$0.00			
		Monument Replacement					SYS	1		\$0.00			
TOTAL FOR ITEM									\$0.00				

Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension
EC	7	ECL Speed Humps	5,000	0.95	24.00	13,334				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	223		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type B, 58S-28					TON	60		\$0.00
		Pavement Message Marking, Paint, Lane Indication Arrow					EA	20		\$0.00
TOTAL FOR ITEM										\$0.00

Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension
EC	8	CCMG Full Depth Patching	0	0.00	24.00	1,224				
		CC 1: Full Depth Patching, Type B, 58S-28					TON	120		\$0.00
		CC 2: Full Depth Patching, Type B, 58S-28					TON	319		\$0.00
		CC 4: Full Depth Patching, Type B, 58S-28					TON	46		\$0.00
		CC 5A: Full Depth Patching, Type B, 58S-28					TON	23		\$0.00
TOTAL FOR ITEM										\$0.00

BID										
Group	Item	Road	Shape Length	Approx. Miles	Road Width	Sq Yds	Unit	Unit Quantities	Price per Unit	Extension
ALT	1	County Road 6 from County Road 9 to County Road 11	5,808	1.10	65.00	41,947				
		Prep Cost (Mill)					LS	1		\$0.00
		Asphalt Milling (2 inches)					SYS	41,947		\$0.00
		Tack Coat					SYS	41,947		\$0.00
		Casting, Manhole, Adjust to Grade					EA	9		\$0.00
		Casting, Water Valve, Adjust to Grade					EA	13		\$0.00
		Joint Adhesive					LFT	5,808		\$0.00
		220 lb/yd ² HMA 12.5 mm, Surface, Type C, 58S-28					TON	4,615		\$0.00
		Line, Paint, Solid, White 4"					LF	12,479		\$0.00
		Line, Paint, Solid, Double Yellow 4"					LF	12,978		\$0.00
		Pavement Markings, Thermoplastic, White, Stop Bar, 24"					LFT	165		\$0.00
		Pavement Markings, Thermoplastic, White, Straight-Right Combo Arrow					EA	6		\$0.00
		Pavement Markings, Thermoplastic, White, Left Turn Arrow					EA	5		\$0.00
		Sawcut for Loop Detector and Sealant					LFT	1,800		\$0.00
		Signal Detector Housing					EA	8		\$0.00
#53 Gravel Shoulders					TON	600		\$0.00		
TOTAL FOR ITEM										\$0.00

Total EC 2025-1										\$0.00
TOTAL 2025-1 CCMG:										\$ -